Bruhath Bengaluru Bengaluru Mahanagara Palike

Name of Work : Improvements of re-asphalting Dasarahalli Main Road & other Roads, S Ramaiah, Ganesha Sawmill, Kempegowda Nagara & Maheshwari Nagara Roads Construction drain and Concrete Main roads & Cross roads of Vidyanagara Dasarahalli Ward No:15 & 39 (6-Works)
Package No. DZ 2017-18-(05)

SL No	Item Name	Unit	Quantity	Rate	
				In Rs	In Words
1	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications II. By Mechanical Means. A. Cement Concrete Grade M-15 &M-20 Page No.137 Item No.18.2 of KPWD S.R2016-2017	Sqm	1174.1	409.47	Four hundred nine rupees forty-seven Paise
2	Removing B.S slab of drain and stacking (Page No 25., I.no.5.32 of KPWD S.R 2016-17).	Sqm	3150	73.59	Seventy three rupees fifty nine paise
3	KSRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average harizintal throw upto 2 meters and an average horizontal lift upto 0.5m, excavated surface leveled and sides neately dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (Page No 142., I.No.19.1 of KPWD S.R 2016-17)	Cum	3280.07	97.32	Ninety seven rupees thirty two paise
4	KSRB4-1.2 Providing and Laying in Position plain cement concerete of mix 1:3:6 with OPC Cement @ 220 Kgs 40 MM and Down Size graded granite metal coarse aggregates @ 0.892 cum and Fine aggragetes @ 0.465cum machine mixed, Machine mixed Concerete laid in Layers not Exceeding 15 cms thick well compacted in foundation including cost of all materials labour HOM of machinery , curing complete as per specifications. Specification No 4.1,4.2 1:3:6 Concerete Page NO 12 I.No. 4.2 of KPWdDS.R 2016-2017	Cum	808.19	5989.01	Five thousand nine hundred and eighty nine rupees one paise
5	KSRB 4-1.5 : Providing and laying in position plain cement concrete cum of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2	Cum	391.13	6577.70	Six thousand five hundred seventy seven and seventy paise
6	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork,curing,including cost of all materials, labour, hire charges of machinery, loading,unloading, lead and lift, transportation etc., complete(Page No 25., I.No.5.27.1 of KPWD S.R 2016-17)	Nos	5955	432.03	Four hundred thirty two and zero three paise

SL No	Item Name	Unit	Quantity	Rate	
				In Rs	In Words
7	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (Page No.182., I.No.24.1 of KPWD S.R.2016-17)	Sqm	938	71.21	Seventy one rupees twenty one paise
8	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406(Page No 158., I.No.20.18 of KPWD S.R 2016-17).	Cum	483.05	1979.72	One Thousand nine hundred Eighty three rupees seventy two paise
9	KSRRB M600 22.6.2Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 ReaffirmecF2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. M20 (at 300Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.43cum) Page No 177 I.No. 22.6.2 of KPWD S.R. 2016-2017	Cum	347.55	6168.23	Six thousand one hundred sixty eight rupees and twenty three paise
10	Providing vaccum dewatering concrete as per direction of engineer in charge of the work Page No 177 I.No. 22.7 of KPWD S.R 2016-2017	Cum	5200.9	106.82	One Hundred six rupees eighty two paise
11	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. Page No 178 I.No.22.8.1 of KPWD S.R. 2016-2017	Cum	1067.4	136.49	One hundred Thirty six rupees fourty nine paise
12	KSRRB 500-2 : Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to rceive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH / Chapter 5 (Page No.161., I.No.21.2 of KPWD S.R 2016-2017)	Sqm	18807	3.56	Three rupees Fifty Six paise

SL No	Item Name	Unit	Quantity	Rate	
				In Rs	In Words
13	KSRRB-3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, applying tack coat on the sides and base of excavation at 2.5kg/sqm as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications MORTH Specification No. 3004.2 (Page No.257., I.No.35.5 of KPWD S.R 2016-2017)	Sqm	1995.2	338.26	Three Hundred thirty eight rupees twenty six paise
14	KSRRB 500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH / Chapter 5 (Page No.161, Item No. 21.7 of KPWD S.R.2016-2017)	Sqm	18807	13.06	Thirteen rupees Six paise
15	KSRRB M500-11 : Providing and laying bituminous Macamdam on prepared surface with crushed coarse aggregates as design mix for base/binding course including loading of agregates with F.E loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity transporting the mixed material in tipper to paver and laying mixed materials paver finisher to the required level and grade, roo lling by power roller to achieve the desired density but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour HOM of machineries complete as per specifications using TPH capacity HMP with sensor paver Gr-II (50mm to 75mm) with 3.3% VG-30 Bitumen (Page No.162, Item No. 21.11.5 of KPWD S.R 2016-17)	Cum	261.9	6210.95	Six Thousand Two Hundred Ten rupees Ninety Five paise
16	KSRRB M500-19 : Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No.500.9 complete in all respects complete as per specifications.MORTH specification no.509 using 40-60 TPH capacity HMP with Sensor paver Gr- II (30mm to 45mm) with 6% VG-30 bitumen (Page No.165, Item No. 21.23.12 of KPWD S.R 2016-17)	Cum	750.84	15283.48	Fifteen thousand two hundred eighty three rupees fourty paise
17	Add Plastic to Bituminous Concrete 8% of Bitumen	Kg	8469.03	30.23	Thirty rupees Twenty Three paise
18	KSRRB M800-13 Road Markig with Hot Applied Thermoplastic compound with Reflectirising glass beads on Bituminous suface:- Providing and laying of Hot applied thermoplastic compund 2.5mm thick including reflectorising glass beads at 250gm/sqm area thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35 the finished surface to be level uniform and pre firm streads and holes complete as per specficaions (Page No.185,I.No.24.15 of KPWD S.R. 2016-2017)	Sqm	1134.76	607.68	Six Hundred Seven rupees Sixty Eight paise

SL No	Item Name	Unit	Quantity	Rate	
				In Rs	In Words
19	KSRRB M800-35. Providing and fixing of road stud 100x 100 mm, die-cast in aluminium, resistant to corrosive effect of salt and grit, fitted with lense reflectors, installed in concrete or asphaltic surface by drilling hole 30 mm upto a depth of 60 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per BS: 873 part 4:1973 complete as per specifications (Page No.189 I.No.24.41 of KPWD S.R 2016-2017)	Nos	3045	402.35	Four Hundred Two rupees Thrity Five paise
20	Refixing B S Slab of Drains and Pointing in C.M (1:30 Page No.25., I.No.5.33 of KPWD S.R.2016-17)	Sqm	3150	90.20	Ninety rupees twenty paise
21	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Cum	702	2053.53	Two thousand fifty three rupees fifty three paise
22	Lead charges for conveying the excavated earth including loading and unloading upto 10kms as per directions (Page No.140 SL.No.5 of KPWD S.R 2016-17)	Cum	3050.57	118.69	One hundred eighteen rupees sixty nine paise

ಎಂ.ಆರ್.ಎಂ.ಬಿ.ಪಿ.ಕೆ.

Executive Engineer
EXECUTIVE ENGINEER - ೬
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57.